BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2015-16/OW/WORK_INDENT21302

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/03/2015-16 Dated: 08-03-2016

Approved Tender Schedule - B

Item No:8

Name of Work: Improvements to drains and asphalting to main and cross roads in A sector in ward no:04.

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri GANGULU REDDY A	
				Rate	Rupees in words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no 138, PWD SR 2014-15)	Cum	207.96	70.0	Rupees seventy and paise zero only
2	Removing B.S slab of drain and stacking	Sqm	485.1	50.0	Rupees fifty and paise zero only
3	Refixing stone slabs of drains and pointing in CM(1:3)	Sqm	485.1	70.0	Rupees seventy and paise zero only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick	Sqm	207.9	600.0	Rupees six hundred and paise zero only
5	KSRRB 4.1.6Providing and laying in position plain cement concrete mix 1:2:4 with cement @240kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted,in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification no 4.1,4.2 (Page.12 & Item No. 4.6)	Cum	35.91	5000.0	Rupees five thousand and paise zero only
6	KSRB 5-14: Providing and constructing precast concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.27)	Cum	84	900.0	Rupees nine hundred and paise and paise zero only
7	KSRB 5-15: Providing and constructing Non load bearing wall with cement concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x10x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.28)	Cum	84	700.0	Rupees seven hundred and paise zero only
8	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	226.8	1400.0	Rupees one thousand four hundred and paise zero only
9	Providing and fixing precast solid concrete kerb stones made out of cc1:2:4 and finished with CM 1:3 plastering and finishing cutting etc.,complete asper specifications and directions of the engineer in charge of the work.P.NO25/S NO5.29.1(PWD SR2014-2015)	Sqm	456.52	350.0	Rupees three hundred fifty and paise zero only
10	KSRB 15-17.5:Applying priming coat over new wood surface and/or wood based surfaces after preparing the surface after throughly cleaning oil,grease,dirt and forign matter,sand papering and knotting liquid wood filler,for varnish including cost of materials,labour,complete as per specificationsP.NO115/15.59)	Sqm	166.72	30.0	Rupees thirty and paise zero only
11	KSRB 15-17.6:Providing and applying painting two coats(excluding priming coat)on new wood surface and/or wood based surfaces with ename paint to give an even shade,cleaning the surface of all dirt,dust and forign matter,sand papering including as per specifications and directions of the engineer in charge of the work.P.NO115/15.60.1)	Sqm	166.72	80.0	Rupees eight and paise zero only

Chief Accounts Controller (Finance)
Yelahanka Zone

...ned on : 30-Oct-2014 14:00

Sl. No.	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri GANGULU REDDY A	
				Rate	Rupees in words
12	KSRRB M400-17: Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification: 406 (PWD SR 2014-15 P.N.154 It 20.18)	Cum	165.17	1400.0	Rupees one thousand four hundred and paise zero only
13	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH SpecificationsNo502 (ITEMNO21.6,Page no157,PWD SR 2014-15)	Sqm	1650	35.0	Rupees thirty five and paise zero only
14	KSRRB M500-18.Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler, transporting the hot mix to work site.laying with a paver finisher to the required grade,levell and alignment, rollingwithsmoothwheeled,vibratoryandtandemrollers to achievethe desired compactionasperMORTHSpecificationclauseno508completeinallrespectscompleteasperspecifications.using100120THcapacity H.M.P with sensor paver gradingI(35-40mm) with 4.5% CRMB55grade(Itemno21.21.1,Pageno16 D 2014-15)	Cum	60.27	10401.6	Rupees ten thousand four hundred one and paise sixty only
15	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2014-15)	Cum	207.96	70.0	Rupees seventy and paise zero only

A. Gangulu Reddy

Signature of the contrator

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Assistant Controller (Finance)
Chief Accounts Office, Yelahanka Zone